



www.ykkap.com



One Bal Harbour Condos - Bal Harbour, FL

YSD 600 T

Thermally Broken Architectural Sliding Balcony Door


The **YSD 600 T** is a thermally broken and architectural rated sliding glass door designed to provide great energy efficiency and occupant comfort. The engineering behind the design provides enhanced structural capabilities without the need to add reinforcing. All panels, fixed and operable, use laminated insulating glass and may be pre-glazed in the shop to take advantage of a controlled environment and less expensive factory labor.

- Variety of configurations available (see back)
- AAMA/WDMA 101/I.S. 2-97/NAFS-02 and AW Performance Grade 75 rated
- Thermally broken by ThermaBond Plus (frame) and MegaTherm iso bars (panels)
- Factory glazing and screen options available
- Standard heavy-duty hardware, including stainless steel rollers and track cover
- Low profile, accessibility-friendly sill option (Available in 2 & 3 panel configurations only)

Thermal Values:


U-Factor:	Values as low as 0.46*
CRF:	Minimum 43 frame and 62 glass

*Based on AAMA 507. Lower values may be achieved through further simulation.



YSD 600 T SPECS		
Base Depth	6"	
Sightline	2" to 2-1/4"	
Config	Pre-Glazed or Factory Glazed / Center Set	
Tested Glass	1" Laminated IGU with Low-E (C.O.G. U-Factor: 0.29)	
Test	Results	Standards
Air Infiltration	0.30 CFM/FT ² (1.10 m ³ /h·m ²) @ 6.24 PSF (299 Pa)	ASTM E 283
Water Infiltration	Static: 20 PSF (958 Pa) Low-Sill: 12 PSF (574 Pa)	ASTM E 331 AAMA 501
Acoustical (1-3/16" IGU)	Laminated STC: 33 Laminated OITC: 30	ASTM E 90 ASTM E 1425
Forced Entry Resistance	Tested in accordance and meets requirements of Performance Grade 10	
		ASTM F 842 TAS 202

Thermal Performance								
Mullion Depth	U-Factor - BTU/hr·ft ² ·°F						CRF	
6" (Standard Threshold)	0.53	0.52	0.50	0.49	0.48	0.46	43	62
Center of Glass	0.30	0.28	0.26	0.24	0.22	0.20	Frame	Glass
AAMA 507							AAMA 1503	




Finish Options	
Type	Standard
Factory Anodized	AAMA 612
Organic Paints	AAMA 2604 AAMA 2605


NOTE: Balcony door configuration will effect the performance specifications

Configurations

Standard Sill



Low Sill



Sill/Threshold Options

We have a standard and low-profile option. The low-profile option is intended to integrate into designs that require accessibility-friendly and low threshold access to balconies and terraces.

Standard Hardware

Pull Handles, Integral Handles, Recessed Handles, Thumbturn and Lockbolt options are available. Please see the Balcony Door Hardware sheet on the Product Guide for more information.



Standard Threshold



Low Profile Threshold

Additional information including CAD details, CSI specs, test reports and installation instructions are found on the Product Guide by clicking this link or visiting www.ykkap.com/commercial/productguide